

# **EHMbrAI**

AI-based versus traditional Engine Health Monitoring:  
a gas path analysis testbed on the CFM56-7B with synthetic ground truth

— (anonymous in the public repository) —

July 3, 2026

Living document: updated at every project milestone.

# Contents

|                                                                                |           |
|--------------------------------------------------------------------------------|-----------|
| <b>Notation and acronyms</b>                                                   | <b>3</b>  |
| <b>1 Introduction</b>                                                          | <b>4</b>  |
| 1.1 Motivation . . . . .                                                       | 4         |
| 1.2 Objective . . . . .                                                        | 4         |
| 1.3 Hypotheses . . . . .                                                       | 5         |
| 1.4 Contributions . . . . .                                                    | 5         |
| 1.5 Document structure . . . . .                                               | 6         |
| <b>2 Background</b>                                                            | <b>7</b>  |
| 2.1 How a two-spool turbofan works . . . . .                                   | 7         |
| 2.2 The subject engine: CFM56-7B26 . . . . .                                   | 7         |
| 2.3 What is measured, and why parameters must be corrected . . . . .           | 8         |
| 2.4 Gas Path Analysis . . . . .                                                | 9         |
| 2.4.1 Health parameters . . . . .                                              | 9         |
| 2.4.2 The linear model . . . . .                                               | 9         |
| 2.4.3 Estimation, and why it is hard . . . . .                                 | 10        |
| 2.4.4 Smearing: a two-parameter toy example . . . . .                          | 10        |
| 2.4.5 Smearing in general . . . . .                                            | 10        |
| 2.5 The physics of degradation . . . . .                                       | 11        |
| <b>3 Methodology and testbed architecture</b>                                  | <b>12</b> |
| 3.1 Overall architecture . . . . .                                             | 12        |
| 3.2 The machine-learning toolbox, briefly . . . . .                            | 13        |
| 3.3 Methodological safeguards . . . . .                                        | 13        |
| 3.4 Reproducibility and infrastructure . . . . .                               | 14        |
| 3.5 Software architecture and computational pipeline . . . . .                 | 14        |
| 3.5.1 Library modules ( <code>src/ehmbrain/</code> ) . . . . .                 | 14        |
| 3.5.2 Executable scripts ( <code>scripts/</code> ) . . . . .                   | 15        |
| 3.5.3 Test suite ( <code>tests/</code> ) . . . . .                             | 16        |
| 3.6 Comparison metrics . . . . .                                               | 16        |
| <b>4 Thermodynamic twin of the CFM56-7B26</b>                                  | <b>17</b> |
| 4.1 What a cycle model is . . . . .                                            | 17        |
| 4.2 Strategy: adapt, don't build from scratch . . . . .                        | 17        |
| 4.3 Design point (WP1.1) . . . . .                                             | 18        |
| 4.4 Calibration against measured data (WP1.2) . . . . .                        | 19        |
| 4.4.1 Data sources and philosophy . . . . .                                    | 19        |
| 4.4.2 Calibration iterations . . . . .                                         | 19        |
| 4.4.3 Idle convergence: diagnosis and cure . . . . .                           | 20        |
| 4.5 Baseline decks (WP1.3) . . . . .                                           | 21        |
| 4.5.1 Corrected-parameter exponents and the corrected-space baseline . . . . . | 22        |

|          |                                                        |           |
|----------|--------------------------------------------------------|-----------|
| 4.6      | Influence coefficient matrix and observability (WP1.4) | 23        |
| 4.6.1    | Health-parameter injection                             | 23        |
| 4.6.2    | The ICM at the reference conditions                    | 23        |
| 4.6.3    | Observability: the quantitative case for hypothesis H2 | 23        |
| 4.6.4    | Thermodynamics cross-check                             | 24        |
| 4.7      | Declared limitations                                   | 24        |
| 4.8      | Automated verification                                 | 25        |
| <b>5</b> | <b>The synthetic fleet: SynCFM56</b>                   | <b>26</b> |
| 5.1      | Generator architecture: linearize, then audit          | 26        |
| 5.2      | Ground-truth trajectories                              | 26        |
| 5.3      | Snapshots and the measurement model                    | 27        |
| 5.4      | Gate audits — including the one that failed            | 29        |
| 5.4.1    | Nonlinearity of the generator                          | 29        |
| 5.4.2    | Difficulty: the audit that failed, and what it taught  | 29        |
| 5.4.3    | Realism                                                | 30        |
| 5.5      | Milestone H2: declared closed                          | 30        |
| <b>6</b> | <b>The traditional EHM pipeline</b>                    | <b>31</b> |
| 6.1      | Pipeline overview                                      | 31        |
| 6.2      | Two detector-design lessons                            | 31        |
| 6.3      | Results on the test fleet (v0 defaults)                | 32        |
| 6.4      | Milestone H3                                           | 32        |
| <b>7</b> | <b>Work in progress and planning</b>                   | <b>35</b> |
| 7.1      | Phase F1: closed                                       | 35        |
| 7.2      | Phase F3: closed                                       | 35        |
| 7.3      | Phase F2: closed                                       | 35        |
| 7.4      | Remaining phases                                       | 35        |
| 7.5      | Milestone log                                          | 35        |
| <b>A</b> | <b>Decision register</b>                               | <b>38</b> |
|          | <b>References</b>                                      | <b>40</b> |

# Notation and acronyms

## Acronyms

|         |                                             |      |                                          |
|---------|---------------------------------------------|------|------------------------------------------|
| BPR     | bypass ratio                                | LOO  | leave-one-out (cross-validation)         |
| CEA     | NASA Chemical Equilibrium with Applications | LPC  | low-pressure compressor (booster)        |
| CI      | continuous integration                      | LPT  | low-pressure turbine                     |
| C-MAPSS | NASA turbofan simulation benchmark          | MAE  | mean absolute error                      |
| EEDB    | ICAO Engine Emissions Databank              | OPR  | overall pressure ratio                   |
| EGT(M)  | exhaust gas temperature (margin)            | PC   | power code: fraction of reference thrust |
| EHM     | engine health monitoring                    | PCS  | Physics-Consistency Score (ours, C5)     |
| FADEC   | full-authority digital engine control       | PHM  | prognostics and health management        |
| FAR     | fuel-air ratio                              | RMSE | root-mean-square error                   |
| FOD     | foreign-object damage                       | RUL  | remaining useful life                    |
| FPR     | false-positive rate                         | SAC  | single annular combustor                 |
| GPA     | gas path analysis                           | SHAP | Shapley additive explanations            |
| HPC     | high-pressure compressor                    | SLS  | sea-level static                         |
| HPT     | high-pressure turbine                       | SVD  | singular value decomposition             |
| ICM     | influence coefficient matrix                | TCDS | type-certificate data sheet              |
| ISA     | international standard atmosphere           | TSFC | thrust-specific fuel consumption         |
| N1, N2  | low-/high-pressure spool speeds             | WLS  | weighted least squares                   |

## Symbols

|                    |                                                            |                                            |                                                  |
|--------------------|------------------------------------------------------------|--------------------------------------------|--------------------------------------------------|
| $\theta, \delta$   | inlet total temperature / pressure ratios to ISA sea level | $\mathbf{H}$                               | influence coefficient matrix                     |
| $\Delta\eta$       | component efficiency deviation [%]                         | $\mathbf{Q}, \mathbf{R}$                   | process / measurement noise covariance           |
| $\Delta\Gamma$     | component flow-capacity deviation [%]                      | $\mathbf{P}_0, \lambda$                    | prior shape / strength of the WLS regularization |
| $\mathbf{x}$       | health-parameter vector (10 components)                    | $N1_c$                                     | corrected fan speed $N1/\sqrt{\theta}$           |
| $\Delta\mathbf{z}$ | measurement deviations from baseline                       | $T_{t4}$                                   | combustor-exit total temperature                 |
| $W_f, F_n$         | fuel flow, net thrust                                      | $\Delta T_{\text{ISA}}$ (dT <sub>s</sub> ) | ambient offset from the ISA day                  |

**Reading order.** Every technical term is defined at first use; Chapter 2 builds the engine and GPA foundations, Section 3.2 the machine-learning toolbox. The hypotheses table (Table 1.1) can be read superficially on a first pass and revisited after those two stops.

# Chapter 1

## Introduction

*This chapter in brief: jet engines degrade invisibly, airlines monitor them through a handful of measurements, and two schools of methods compete to interpret those measurements. This project builds a level playing field to compare them. If you are new to the field, skim the hypotheses table on first read and return to it after Chapter 2.*

### 1.1 Motivation

A commercial jet engine degrades from its very first flight. Dust and pollution stick to compressor blades, hot-section parts creep and oxidize, tip clearances open up, seals wear. The airline cannot see any of this directly —the engine stays on the wing for years— so it watches the engine’s *symptoms* instead: the temperatures, pressures, shaft speeds and fuel flow recorded on every flight. The discipline that turns those symptoms into maintenance decisions is called *Engine Health Monitoring* (EHM). The stakes are large: a single shop visit for an engine overhaul costs millions of dollars, and an unscheduled engine removal disrupts an entire fleet schedule.

The classical analytical core of EHM, in use since the 1970s, is *Gas Path Analysis* (GPA) [1]. The idea: each physical fault (a dirty compressor, an eroded turbine) leaves a characteristic fingerprint on the measured parameters; by inverting a thermodynamic model of the engine, one can estimate *which* component has deteriorated and *by how much* from the measurements alone. Around GPA the industry built a mature toolbox —baseline models, exponential trend smoothing, Kalman filters, expert fault-isolation rules [2]— which this project collectively calls *traditional EHM*.

Over the last decade, machine learning has produced striking results in the adjacent research field of prognostics: predicting the *Remaining Useful Life* (RUL) of an engine, i.e. how many flights remain before it must come off the wing, mostly on synthetic benchmark datasets such as NASA’s C-MAPSS [3] and N-CMAPSS [4]. Yet the literature has a structural weakness: **AI methods are almost never compared against a traditional pipeline implemented with equal care**, on the same data, with the same metrics and the same tuning effort. The result is a stream of comparisons against straw men, which makes it impossible to know what AI actually contributes, under which conditions, and at what cost.

### 1.2 Objective

This project builds a reproducible testbed in which both EHM families —traditional and AI-based— observe *exactly the same data* from a synthetic fleet of CFM56-7B26 turbofans and are scored with *exactly the same metrics*. The methodological key is that the synthetic data carries **complete ground truth**: the true health state of every engine component (its efficiency and flow-capacity deviations, defined in Section 2.4) at every flight. With real airline data this is

impossible —nobody knows the true internal state of an engine on the wing— but with synthetic data one can measure not only whether a method detects or predicts well, but whether it *attributes the damage to the correct component*. That attribution question is precisely where traditional GPA is weakest (the *smearing* phenomenon, Section 2.4) and where AI is least transparent (the black-box problem).

Since neither a performance model of the engine nor degradation data were available to the project, both are built from scratch: a thermodynamic “digital twin” of the CFM56-7B26 in pyCycle [5], calibrated against certified public data (Chapter 4), and a fleet degradation generator with physically derived fault signatures (Chapter 5).

### 1.3 Hypotheses

Each hypothesis is formalized with quantitative thresholds *before* any test-set result is seen (the pre-registration protocol of Section 3.3). All are tested with a Wilcoxon signed-rank test paired by engine, Holm correction for multiple comparisons ( $\alpha = 0.05$ ), and BCa bootstrap confidence intervals. In plain words: for every comparison we check that the improvement is statistically significant, not a fluke of one lucky engine. The table below necessarily uses terms defined later—the GPA quantities in Chapter 2, the machine-learning methods in Section 3.2, every metric in the metrics section of Chapter 3, and all acronyms in the notation chapter— so it is meant to be skimmed now and revisited after those stops.

Table 1.1: Project hypotheses and their confirmation criteria.

| ID | Hypothesis                                                                  | Confirmation criterion                                                                                                                                                                           |
|----|-----------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| H1 | AI detects faults earlier and with fewer false alarms than trend monitoring | median lead time $\geq +20\%$ and false-positive rate $\leq 0.5\times$ versus trending, at a fixed recall of 0.9; $p < 0.05$                                                                     |
| H2 | AI isolates faults with overlapping signatures better                       | +10 percentage points of isolation accuracy on the “confusable” subset (fault signatures less than $15^\circ$ apart in the influence-matrix space) versus weighted-least-squares GPA; $p < 0.05$ |
| H3 | AI predicts RUL better                                                      | simultaneous improvement in RMSE and in the asymmetric NASA PHM08 score; $p < 0.05$                                                                                                              |
| H4 | The physics-informed hybrid dominates when data is scarce                   | RUL RMSE $\leq$ pure AI with 100 % of the training data and strictly better with 10 % and 25 %; $p < 0.05$                                                                                       |
| H5 | Conformal intervals are better calibrated than the Kalman covariance        | smaller $ \text{empirical coverage} - 0.9 $ with mean interval width no worse than +20 %                                                                                                         |

Refuting any hypothesis is itself a publishable result: pre-registration is what makes the refutation credible. Reformulating hypotheses after the repository tag `prereg-v1` is forbidden.

### 1.4 Contributions

- C1. SynCFM56:** the first public synthetic GPA dataset for a specific commercial engine (CFM56-7B26), with per-flight health-parameter ground truth and an ACARS-style snapshot format (one takeoff report and one cruise report per flight, the way real airline EHM data actually arrives), more realistic than the continuous time series of C-MAPSS.
- C2.** A head-to-head comparison under a **pre-registered protocol** with a symmetric tuning budget (the same number of Optuna trials) for both families.
- C3.** A physics-informed hybrid with three separately ablated mechanisms: residual features against the digital twin, physically constrained loss functions, and GPA→ML stacking.

- C4. Compared uncertainty quantification: conformal-prediction RUL intervals versus the Kalman filter covariance.
- C5. The **Physics-Consistency Score (PCS)**: a new explainability metric that projects SHAP attributions into the physical health-parameter space through the influence coefficient matrix.
- C6. A determinability map: a sensors  $\times$  noise  $\times$  data-size ablation showing *when* each approach wins.
- C7. Sim-to-real validation: the full methodology is re-run on N-CMAPSS to check that the method ranking is not an artifact of our own simulator.

## 1.5 Document structure

Chapter 2 builds the technical foundations assuming no prior knowledge of jet engines or GPA: how a turbofan works, what is measured on the wing, and the mathematics of gas path diagnosis. Chapter 3 describes the testbed architecture and the methodological safeguards. Chapter 4 documents the thermodynamic twin of the CFM56-7B26 and its calibration against certified data—the work completed to date—with quantitative evidence of every step. Chapter 7 summarizes the remaining phases and their acceptance criteria.

# Chapter 2

## Background

*This chapter in brief: how a turbofan works and what its two spools are; which handful of numbers an airline actually sees; why raw readings must be corrected before comparison (with a worked example); how gas path analysis turns corrected deviations into a health diagnosis; a two-line toy problem showing exactly how that diagnosis fails (smearing); and how real engines physically degrade. Everything later builds on these six ideas.*

This chapter assumes no prior knowledge of gas turbines. It introduces the engine, the measurements available in service, the mathematics of gas path diagnosis, and the physics of degradation —everything needed to follow the rest of the document.

### 2.1 How a two-spool turbofan works

A turbofan produces thrust by accelerating air backwards. Air enters through the *fan* (the large visible rotor); most of it —the *bypass* stream— goes around the core and exits through the bypass nozzle, producing the majority of the thrust. The rest enters the *core*: it is compressed by a low-pressure compressor (the *booster*) and a high-pressure compressor (HPC), heated by burning fuel in the *combustor*, and expanded through a high-pressure turbine (HPT) and a low-pressure turbine (LPT) that extract the work needed to drive the compressors, before leaving through the core nozzle.

The machine is arranged in two mechanically independent *spools* (concentric shafts):

- the **low-pressure (LP) spool**: fan + booster driven by the LPT, rotating at speed **N1**;
- the **high-pressure (HP) spool**: HPC driven by the HPT, rotating at speed **N2**.

The ratio of bypass to core mass flow is the *bypass ratio* (BPR); the ratio of compressor exit pressure to inlet pressure is the *overall pressure ratio* (OPR). Higher BPR and OPR generally mean better fuel efficiency, measured as *thrust-specific fuel consumption* (TSFC): fuel flow per unit of thrust. Figure 2.1 shows the layout and the station numbers used throughout this document.

### 2.2 The subject engine: CFM56-7B26

The CFM56-7B (CFM International, a Safran–GE joint venture) powers the Boeing 737NG family and is one of the most widely operated commercial engines in history, which guarantees abundant public type data. The **-7B26** variant (117 kN takeoff thrust, Boeing 737-800) is chosen as the most common one. Its type-certificate data sheet (TCDS EASA E.004, issue 07 [6]) describes: a single-stage fan, 3-stage booster, 9-stage HPC, annular combustor, single-stage HPT






Figure 2.1: Two-spool separate-flow turbofan layout with the SAE station numbers used in this document. The EGT probe of the real CFM56-7B sits inside the LPT (station 49.5); this model uses station 45 (HPT exit) as its consistent EGT proxy.

and 4-stage LPT, governed by a dual-channel FADEC (a full-authority digital engine control—the computer that meters fuel). The pilot-facing thrust-setting parameter is N1, not engine pressure ratio.

Table 2.1: Certified CFM56-7B26 data used as the calibration contract. Sources: TCDS EASA E.004 issue 07 [6] and the ICAO Engine Emissions Databank, edition 03/2026, UID 3CM033 [7].

| Quantity                                 | Value                                            | Source | Status   |
|------------------------------------------|--------------------------------------------------|--------|----------|
| Takeoff thrust                           | 11 699 daN (= 116.99 kN)                         | TCDS   | verified |
| Maximum continuous thrust                | 11 521 daN                                       | TCDS   | verified |
| N1 redline (104 %)                       | 5382 rpm $\Rightarrow$ 100 % = 5175 rpm          | TCDS   | verified |
| N2 redline (105 %)                       | 15 183 rpm $\Rightarrow$ 100 % = 14 460 rpm      | TCDS   | verified |
| Max. EGT, takeoff / continuous           | 950 °C / 925 °C (displayed)                      | TCDS   | verified |
| Dry weight                               | 2386 kg                                          | TCDS   | verified |
| Bypass ratio                             | 5.1                                              | EEDB   | verified |
| Pressure ratio (sea-level static, rated) | 27.61                                            | EEDB   | verified |
| Fuel flow at 100/85/30/7 % $F_{00}$      | 1.221 / 0.999 / 0.338 / 0.113 kg s <sup>-1</sup> | EEDB   | verified |

Two subtleties from the TCDS matter for modeling and are frequently overlooked:

- The certified *exhaust gas temperature* (EGT)—the single most important health indicator, because it rises as the engine deteriorates—is measured at station **T49.5** (the stage-2 LPT nozzle), *not* at the HPT exit. Moreover, the *displayed* cockpit value adds a “shunt” function of +30 °C (for single-annular-combustor engines, active above 8500 rpm N2) plus a model-dependent “trim” (zero for the -7B26).
- Air bleed limits (air extracted from the compressor for the aircraft’s cabin and anti-ice systems) are tabulated per extraction stage and shaft speed; at rated speed the 9th-stage bleed is capped at 7 % of core flow.

## 2.3 What is measured, and why parameters must be corrected

Engine locations are numbered per the SAE ARP755A standard [8]: station 2 is the fan inlet, 21 the fan exit, 25 the HPC inlet, 3 the HPC exit, 4 the combustor exit, 45 the HPT exit, and 5 the LPT exit. The measurements available in airline service (the “cockpit set”) are N1, N2, EGT and fuel flow  $W_f$ ; some installations add pressures and temperatures at stations 25 and 3.

A raw measurement is meaningless on its own because it depends on the day: the same healthy engine reads a higher EGT on a hot day at a high-altitude airport than on a cold day at

sea level. To compare flights, measurements are *corrected* to standard sea-level conditions using  $\theta = T_{t2}/288.15\text{ K}$  and  $\delta = P_{t2}/101.325\text{ kPa}$  (the ratios of inlet total temperature and pressure to their standard-day values):

$$N_{\text{corr}} = \frac{N}{\sqrt{\theta}}, \quad W_{f,\text{corr}} = \frac{W_f}{\delta \theta^a}, \quad \text{EGT}_{\text{corr}} = \frac{\text{EGT}}{\theta}. \quad (2.1)$$

The exponent  $a$  (typically 0.5–0.7) is often copied from generic tables; here it will instead be fitted by regression on sweeps of our own thermodynamic model, removing a classical source of systematic baseline error.

**Worked example.** A healthy engine reads 880 K of EGT on a standard day ( $\theta = 1$ ). On an ISA+30 day the inlet runs at 318 K, so  $\theta = 318/288.15 = 1.104$ , and the same healthy engine reads 966 K. A naive comparison would report an “86 K deterioration” where none exists. Corrected with the fitted exponent  $a = 0.95$ :  $966/1.104^{0.95} = 879\text{ K}$  — the hot-day reading collapses onto the standard-day one, and only *genuine* health changes remain visible. This is why every deviation in this project is computed in corrected space.

## 2.4 Gas Path Analysis

### 2.4.1 Health parameters

GPA describes the internal state of the engine with two numbers per turbomachine: the deviation of its *isentropic efficiency*  $\Delta\eta$  (how much of the ideal work it actually achieves — dirt and wear reduce it) and the deviation of its *flow capacity*  $\Delta\Gamma$  (how much corrected flow it swallows at a given speed — fouling reduces it in compressors; turbine erosion, which opens the effective nozzle area, increases it). With five turbomachines (fan, booster, HPC, HPT, LPT) the health state is the 10-component vector

$$\mathbf{x} = [\Delta\eta_{\text{fan}}, \Delta\Gamma_{\text{fan}}, \Delta\eta_{\text{LPC}}, \Delta\Gamma_{\text{LPC}}, \Delta\eta_{\text{HPC}}, \Delta\Gamma_{\text{HPC}}, \Delta\eta_{\text{HPT}}, \Delta\Gamma_{\text{HPT}}, \Delta\eta_{\text{LPT}}, \Delta\Gamma_{\text{LPT}}]^T, \quad (2.2)$$

expressed in percent relative to a new engine.  $\mathbf{x}$  is what maintenance actually wants to know, and it is not directly measurable on the wing.

### 2.4.2 The linear model

What *is* measurable are deviations  $\Delta\mathbf{z}$  of the corrected parameters from a *baseline* (the value a new engine would show at the same operating condition  $\mathbf{u}$ : altitude, Mach number, N1 setting, ambient temperature deviation, bleed status). For the small deviations typical of in-service deterioration, measurement and health deviations are related linearly:

$$\Delta\mathbf{z} = \mathbf{H}(\mathbf{u}) \mathbf{x} + \mathbf{S} \mathbf{b} + \mathbf{v}, \quad \mathbf{v} \sim \mathcal{N}(\mathbf{0}, \mathbf{R}), \quad (2.3)$$

where  $\mathbf{H}$  is the *influence coefficient matrix* (ICM) — the Jacobian  $\partial\mathbf{z}/\partial\mathbf{x}$ , i.e. a table of “if the HPT loses 1 % efficiency, EGT rises by this much and fuel flow by that much” — computed by finite differences on the thermodynamic model at the operating condition  $\mathbf{u}$ ;  $\mathbf{b}$  collects sensor biases and  $\mathbf{S}$  is the *selection matrix* that routes each bias to its own measurement row — one column per biased sensor, all zeros except a single one, so that a bias on the EGT probe shifts only the EGT equation. Estimating  $\mathbf{b}$  alongside  $\mathbf{x}$  is optional and costs observability; an undetected drift therefore fools the estimator, which is exactly the sensor fault Chapter 5 injects. Finally  $\mathbf{v}$  is measurement noise with covariance  $\mathbf{R}$ .

### 2.4.3 Estimation, and why it is hard

Inverting Eq. (2.3) is an ill-posed problem. With 4 cockpit measurements and 10 unknowns the system is underdetermined ( $\text{rank}(\mathbf{H}) \leq 4$ ): infinitely many health states explain the same measurements. The weighted-least-squares (WLS) answer regularizes the inversion with prior knowledge of plausible deterioration:

$$\hat{\mathbf{x}} = \left( \mathbf{H}^T \mathbf{R}^{-1} \mathbf{H} + \lambda \mathbf{P}_0^{-1} \right)^{-1} \mathbf{H}^T \mathbf{R}^{-1} \Delta \mathbf{z}, \quad (2.4)$$

where the two regularization pieces play distinct roles:  $\mathbf{P}_0$  (a diagonal matrix of expected deterioration magnitudes squared) sets the *shape* of the prior — which parameters are allowed to move more — while the scalar  $\lambda$  sets its *strength*, trading fidelity to the measurements against fidelity to the prior.  $\lambda$  is a tuning knob of the traditional pipeline and receives the same optimization budget as the AI’s hyperparameters (Section 3.3).

Because deterioration evolves slowly over thousands of flights, tracking it as a *random walk* with a Kalman filter improves on flight-by-flight estimation. The Kalman filter is a recursive estimator that blends the previous health estimate with each new measurement, weighting each by its uncertainty:

$$\mathbf{x}_k = \mathbf{x}_{k-1} + \mathbf{w}_k, \quad \mathbf{w} \sim \mathcal{N}(\mathbf{0}, \mathbf{Q}); \quad \mathbf{z}_k = \mathbf{H}(\mathbf{u}_k) \mathbf{x}_k + \mathbf{v}_k, \quad (2.5)$$

with process noise  $\mathbf{Q}$  calibrated to realistic degradation rates and the state optionally augmented with sensor biases [2]. At recorded compressor-wash events the recoverable part of the state is reset.

### 2.4.4 Smearing: a two-parameter toy example

Before the formal statement, a miniature GPA problem shows the failure mode this whole project revolves around. Suppose only two health parameters (HPC and HPT efficiency) and two measurements (EGT and  $W_f$  deviations, in %), with influence matrix

$$\mathbf{H} = \begin{pmatrix} 1.0 & 0.9 \\ 0.5 & 0.5 \end{pmatrix},$$

whose columns —the two fault signatures— point in nearly the same direction. Let the truth be an HPC fault only:  $\mathbf{x} = (-1, 0)^T$ , giving exact measurements  $\Delta \mathbf{z} = (-1.0, -0.5)^T$ , and indeed  $\mathbf{H}^{-1} \Delta \mathbf{z} = (-1, 0)^T$  recovers it. Now perturb the first measurement by just +0.1 (a 10 % error, comparable to one noise standard deviation):

$$\mathbf{H}^{-1} \begin{pmatrix} -0.9 \\ -0.5 \end{pmatrix} = \begin{pmatrix} 10 & -18 \\ -10 & 20 \end{pmatrix} \begin{pmatrix} -0.9 \\ -0.5 \end{pmatrix} = \begin{pmatrix} 0 \\ -1 \end{pmatrix}.$$

The estimate now says: HPC healthy, *HPT* degraded by 1 % — a single noise-sized error flipped the diagnosis to the wrong component entirely. Nothing is wrong with the algebra; the information simply is not in the measurements when signatures nearly coincide.

### 2.4.5 Smearing in general

That is *smearing*: when  $\mathbf{H}$  is ill-conditioned —fault signatures nearly parallel— noise makes the estimator distribute a fault that is physically concentrated in one component across several, or attribute it to the wrong one; it is the classical weakness of linear GPA [9]. A singular-value decomposition (SVD) of the ICM quantifies this weakness (rank, condition number, angles between fault signatures) and defines the “confusable” subset used by hypothesis H2: fault pairs whose signatures are less than  $15^\circ$  apart.

Table 2.2: Degradation mechanisms modeled in this project and their typical effects, per the literature [10, 11].

| Mechanism                   | Component     | Typical effect                                              | Time profile              | Recoverable           |
|-----------------------------|---------------|-------------------------------------------------------------|---------------------------|-----------------------|
| Fouling (dirt buildup)      | fan, LPC, HPC | $\Delta\Gamma -1\ldots-4\%$ ; $\Delta\eta -0.5\ldots-2.5\%$ | saturating exponential    | wash recovers 30–70 % |
| Erosion                     | compressors   | $\Delta\eta -0.5\ldots-1.5\%$                               | slow linear               | no                    |
| Tip-clearance opening       | HPC/HPT       | $\Delta\eta -0.5\ldots-1.5\%$                               | fast initially, then slow | no                    |
| Hot-section deterioration   | HPT           | $\Delta\eta -1\ldots-3\%$ ; $\Delta\Gamma +1\ldots+2\%$     | linear, accelerating      | no                    |
| Foreign-object damage (FOD) | fan/HPC       | step $\Delta\eta -0.5\ldots-2\%$                            | step (Poisson arrivals)   | no                    |
| Sensor drift                | any probe     | e.g. EGT $+1\ldots+5\text{ }^\circ\text{C}$ per 1000 cycles | ramp                      | recalibration         |

## 2.5 The physics of degradation

The aggregate observable effect is the erosion of the *EGT margin*: the distance between the EGT reached on a hot-day takeoff and its certified limit. A new engine has 70–100 °C of margin; when the margin reaches zero the engine can no longer legally produce rated takeoff thrust on a hot day and must come off the wing. Its characteristic pattern over an engine’s life —fast early loss, slower steady erosion, sawtooth recoveries at each compressor wash— is what the fleet generator of phase F2 must reproduce. Table 2.2 summarizes the mechanisms, their signatures and their time profiles; its magnitudes parameterize that generator.

## Chapter 3

# Methodology and testbed architecture

*This chapter in brief: the project is six chained phases, each ending in a pass/fail gate (Fig. 3.1). Four safeguards keep the AI-versus-traditional comparison honest; one section explains every machine-learning tool by name before it is used; and the software inventory maps each program to its role. Read Section 3.2 even if you skip the rest.*

### 3.1 Overall architecture




Figure 3.1: The six project phases, their gates (H1–H6) and their key artifacts. Everything to the left of an arrow must pass its gate before the next phase starts.

The testbed is organized in six chained phases, each closed by a milestone (*gate*) with a measurable acceptance criterion:

- F1. Thermodynamic twin** of the CFM56-7B26 in pyCycle: design point, off-design behavior, baseline decks over the flight envelope (pre-computed tables of what a healthy engine reads at every operating condition) and the influence coefficient matrix. Gate H1: error  $\leq 3\%$  against certified data at the anchor points.
- F2. Synthetic fleet generator** (SynCFM56): per-mechanism health trajectories, a hierarchical fleet of  $\sim 100$  engines run to failure, a sensor model (noise, bias, quantization, missing data) and ACARS-style snapshots with ground truth. Gate H2: dataset audited for realism and difficulty, no leakage between data splits, and a written datasheet.
- F3. Traditional EHM** reference: baselines and smoothed deviations, trend monitoring with persistence rules, WLS GPA (Eq. (2.4)), Kalman GPA (Eq. (2.5)), expert-rule fault isolation, and RUL by robust extrapolation of the EGT margin. Gate H3: full metrics on the test set.
- F4. AI-based EHM**: anomaly detection (autoencoders, Isolation Forest), multi-class fault diagnosis (gradient boosting, neural networks), RUL prognosis (LSTM/TCN/Transformer sequence models), the physics-informed hybrid, conformal uncertainty and physical explainability (PCS). Gate H4.

**F5. Pre-registered comparative evaluation:** common metrics, statistical tests, ablations, and sim-to-real validation on N-CMAPSS. Gate H5.

**F6.** Case studies, interactive dashboard, and final writing. Gate H6.

## 3.2 The machine-learning toolbox, briefly

For self-containedness, the AI techniques named above in one paragraph each:

**Autoencoder (anomaly detection).** A neural network trained to compress and then reconstruct *healthy* data. Fed a degraded snapshot, it reconstructs it poorly; the reconstruction error is the anomaly score. No fault labels needed.

**Isolation Forest (anomaly detection).** An ensemble of random trees; anomalous points are isolated in fewer random splits than normal ones. A classical non-neural baseline.

**Gradient boosting / XGBoost (diagnosis).** An ensemble of small decision trees, each correcting the errors of the previous ones. State of the art on tabular data; predicts the fault class of a snapshot window.

**LSTM, TCN, Transformer (RUL prognosis).** Three sequence-model families —recurrent, convolutional and attention-based— that consume a sliding window of past snapshots and regress the remaining useful life. Compared against each other in F4.

**Conformal prediction (uncertainty).** A distribution-free wrapper: from the model’s errors on a calibration set it builds prediction intervals with a mathematically guaranteed coverage rate (e.g. 90 %), regardless of the underlying model.

**SHAP (explainability).** Assigns each input feature its contribution to one specific prediction (a game-theoretic attribution). The PCS (contribution C5) projects these attributions through the ICM into health-parameter space to test their physical coherence.

**Optuna (tuning).** An automated hyperparameter search library; a “trial” is one training run with a candidate configuration. Both EHM families get the same trial budget.

Supporting infrastructure named later: *DVC* versions datasets the way git versions code; *MLflow* records every training run (configuration, metrics, artifacts) so experiments are traceable and repeatable.

## 3.3 Methodological safeguards

The credibility of an AI-versus-traditional comparison depends on eliminating the biases that plague the literature. Four safeguards are adopted:

**Pre-registration.** Hypotheses (Table 1.1), metrics, data splits (with file hashes), statistical tests and the stopping rule are frozen in the repository under a git tag (**prereg-v1**) *before* the test set is evaluated. This borrows a standard practice from medicine: you state what would convince you before looking at the answer, so you cannot move the goalposts afterwards.

**Symmetric tuning budget.** Every method has knobs. The traditional pipeline’s (alert thresholds, regularization  $\lambda$ , Kalman  $\mathbf{Q}$ , smoothing windows) and each AI family’s hyperparameters are tuned with the *same number* of automated search trials (Optuna), using only the training and validation engines.

**Split by engine.** The fleet is divided 70/10/20 engines into training, validation and test sets, and no engine ever appears in two sets. Splitting by flight instead of by engine—a common mistake—would let a model memorize an engine’s individual quirks and score unrealistically well. An automated leakage check runs in continuous integration.

**A strong baseline.** The traditional pipeline is implemented with the same care as the AI, every expert rule documented with its physical justification; smearing is *measured* against ground truth, not assumed.

## 3.4 Reproducibility and infrastructure

The entire project is a public repository<sup>1</sup> with a reproducible environment: Python 3.11 managed with `uv` and a fully pinned dependency lockfile; `pyCycle` 4.4 on `OpenMDAO` [12]; declarative YAML configuration; and automated tests (`pytest`) executed by continuous integration—a service that re-runs the whole test suite on every change, so a regression cannot land silently. Data and experiments of later phases will be versioned with `DVC` and `MLflow` respectively.

Three concrete decisions illustrate the intended standard of rigor:

- **A versioned calibration contract.** The model’s numerical targets (Table 2.1) live in a single file (`conf/cfm56_7b_targets.yaml`) carrying value, tolerance, source and status (`VERIFIED/TO_VERIFY`) per entry. Both the model runners and the tests read that file: changing a target is a visible version-control event, never a silent edit.
- **Dependency canary tests.** During environment setup, an incompatibility between `pyCycle` 4.4 and `numpy`  $\geq 2$  was discovered (a failure inside the tabular thermodynamics package). The fix pins `numpy`  $< 2$ , and a smoke test that runs a complete engine cycle executes on every CI run, so any future dependency upgrade that breaks the solver fails loudly and immediately.
- **Auto-generated evidence.** Every result figure and table in this document is produced by a script (`scripts/make_report_assets.py`) that solves the model and writes the PDFs, the  $\text{\LaTeX}$  table files (`paper/report/tables/*.tex`) and a provenance file (`assets.json`). No result number is ever copied by hand.
- **Compute-efficiency norms.** The repository carries binding engineering norms (`docs/engineering-norms.md`): long decomposable computations run in parallel across CPU cores (thermodynamic sweeps and ICM columns use one worker process per core—these are scalar Newton solves that gain nothing from a GPU), while the tensor workloads of phase F4 (network training, SHAP) run on the GPU (Apple-silicon MPS backend on the development machine).

## 3.5 Software architecture and computational pipeline

This section is the complete inventory of the project’s code: what each program does, how it does it, and what flows between them. It is updated whenever code lands.

### 3.5.1 Library modules (`src/ehmbrain/`)

**`perf/cycle.py` — the engine model.** Defines four model classes and their builders.

---

<sup>1</sup><https://github.com/cedarcreeks/EHMbrAI>

- `CFM56(pyc.Cycle)`: one thermodynamic point. Builds the component graph (inlet, fan, splitter, booster, HPC with three bleed ports, post-compressor bleed, combustor, cooled HPT/LPT, ducts, two convergent nozzles, two shafts, performance block) and its balance system. In *design* mode the four balances solve mass flow for thrust, fuel–air ratio for  $T_{t4}$ , and both turbine expansion ratios for zero net shaft power. In *off-design* mode they solve mass flow and bypass ratio to hold the design nozzle throat areas, both spool speeds for shaft power balance, and fuel–air ratio according to the throttle mode: `T4` (rating temperature), `percent_thrust` (a fraction of a reference thrust) or `N1` (hold fan speed, the CFM56 rating parameter, implemented through a passthrough component because the speed is itself another balance’s output). Each point carries its own Newton solver (tolerance  $10^{-8}$ , Armijo–Goldstein line search, subsystem solves enabled).
- `MPCFM56(pyc.MPCycle)`: DESIGN + the four SLS anchors A2–A5 as thrust-matched `percent_thrust` points. Used for calibration (Section 4.4).
- `MPCFM56Study`: DESIGN + one off-design point whose five turbomachine map scalars (efficiency and flow) pass through multiplier components (`health_<comp>.eta_fac/flow_fac`); setting a factor to  $1 + \Delta$  imposes a health deviation. Used for the ICM and, in F2, for degraded-fleet snapshots.
- `MPCFM56Deck`: DESIGN + `OD_max` (maximum thrust at the rating  $T_4$ ) + `OD_pt` (a commanded fraction of that maximum). Used for the baseline decks.
- Builders (`build_problem`, `build_study_problem`, `build_deck_problem`) return solver-ready problems with all design inputs and balance initial guesses set; `solve_anchors()` encapsulates the idle power continuation ( $0.30 \rightarrow 0.07$ ); `snapshot()` reads the full sensor set at a point; `set_health()` imposes a health-deviation dictionary.

**perf/icm.py — GPA sensitivity analysis.** `compute_icm()` builds a Study problem per health parameter (in parallel worker processes, norm N1), perturbs it  $\pm 0.5\%$  at constant N1 and forms the central-difference column in %-per-%; `svd_report()` returns rank, singular values and condition number; `signature_angles()` the pairwise angles between fault signatures; and `confusable_pairs()` the sub- $15^\circ$  subset that instantiates hypothesis H2.

**common/corrections.py — corrected parameters.** ISA atmosphere (`isa_static`), ram-corrected  $\theta/\delta$  at the fan face (`theta_delta`), the exponent regression `fit_correction_exponents()` ( $\log Y$  against a cubic polynomial in  $\log$  corrected speed plus  $a \log \theta + b \log \delta$ , solved by least squares) and `correct()` to apply the fitted law.

### 3.5.2 Executable scripts (scripts/)

Each script is a pipeline stage writing versioned artifacts under `data/processed/`:



| Script                                  | Function and outputs                                                                                                                                                                                                                                                                         |
|-----------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <code>run_design_point.py</code>        | Solves the design point, checks the five WP1.1 acceptance windows against the contract; nonzero exit on failure.                                                                                                                                                                             |
| <code>run_anchors.py</code>             | Solves DESIGN + A2–A5 with the idle continuation and compares fuel-flow/OPR predictions to the EEDB (gated tolerances); prints the verdict table.                                                                                                                                            |
| <code>make_decks.py</code>              | Envelope sweep for the baseline decks: independent (altitude, Mach) blocks in parallel processes, warm continuation inside a block, cold-rebuild recovery (norm N2), then a per-channel parallel leave-one-out audit. → <code>baseline_deck.parquet</code> , <code>deck_report.json</code> . |
| <code>make_corrected_baseline.py</code> | Fits the correction exponents on the deck and re-runs the leave-one-out audit in corrected space. → <code>corrected_baseline.json</code> .                                                                                                                                                   |
| <code>make_icm.py</code>                | ICM at the six-point operating grid (columns in parallel), SVD and confusability analysis. → <code>icm_&lt;point&gt;.npz</code> , <code>icm_report.json</code> .                                                                                                                             |
| <code>cea_crosscheck.py</code>          | Re-solves the design point with CEA thermodynamics and reports deltas against tabular. → <code>cea_crosscheck.json</code> .                                                                                                                                                                  |
| <code>make_report_assets.py</code>      | Regenerates every figure and table of this document from the model and the artifacts above (norm N4). → <code>paper/report/figures/*.pdf</code> , <code>paper/report/tables/*.tex</code> , <code>assets.json</code> .                                                                        |

The data flow is linear: `conf/cfm56_7b_targets.yaml` (the contract) feeds the model classes; runners and `make_*` scripts solve them and write `data/processed/*` artifacts; `make_report_assets.py` turns artifacts into report evidence; the tests gate every stage.

### 3.5.3 Test suite (tests/)

Sixteen tests, all run in CI on every change: environment smoke (the vendored pyCycle example end-to-end); design-point convergence and acceptance windows; anchor convergence, fuel-flow and OPR tolerances, and N1/N2 redlines; the Study self-consistency property (healthy off-design at design N1 reproduces the design point); ICM physical signs and rank-3 cockpit underdetermination; and the corrections module (ISA values,  $\theta/\delta$ , exponent-fit recovery on synthetic data with known truth).

## 3.6 Comparison metrics

Both families are scored with identical metrics. For detection: lead time (how many flights before the ground-truth event the method raises a sustained alert), false alarms per thousand flights, F1 and precision-recall AUC. For isolation: top-1/top-2 accuracy, macro-F1, a *smearing index* (the fraction of  $\|\hat{\mathbf{x}}\|_1$  assigned to healthy components) and the PCS. For health estimation: RMSE of  $\hat{\mathbf{x}}$  against ground truth. For RUL: RMSE, MAE, the NASA PHM08 score

$$S = \sum_i s_i, \quad s_i = \begin{cases} e^{-d_i/13} - 1 & d_i < 0 \\ e^{d_i/10} - 1 & d_i \geq 0 \end{cases}, \quad d_i = \widehat{\text{RUL}}_i - \text{RUL}_i, \quad (3.1)$$

which penalizes late predictions more than early ones (a late removal risks an in-flight shutdown; an early one merely wastes some life). Two further prognostic metrics need definitions:  $\alpha$ - $\lambda$  *accuracy* is the fraction of predictions falling within  $\pm\alpha$  (here 20 %) of the true RUL when evaluated at specified life fractions  $\lambda$  (here 50, 70 and 90 % of the way to failure) — it asks “was the prediction acceptable at mid-life? near the end?”; the *prognostic horizon* is the earliest moment from which the prediction stays within the  $\pm\alpha$  band for the rest of the engine’s life — longer horizons mean earlier trustworthy warnings. For uncertainty: empirical versus nominal interval coverage (does the “90 %” interval actually contain the truth 90 % of the time?) and mean interval width (narrow honest intervals are the goal; wide intervals are trivially calibrated but useless).

## Chapter 4

# Thermodynamic twin of the CFM56-7B26

*This chapter in brief: a virtual CFM56-7B26 is built in pyCycle by adapting a validated NASA example, calibrated against certified data (its fuel-flow predictions land within 3 % of measured test-bed values), and then interrogated for the two artifacts everything else consumes: the healthy-engine baseline decks and the influence coefficient matrix, whose geometry quantifies exactly how blind the cockpit sensor set is.*

This chapter documents the completed part of phase F1: the CFM56-7B26 performance model in pyCycle [5], its design point (work package WP1.1) and its off-design calibration against certified measured data (WP1.2). All result figures and tables are produced by the evidence-generation script (Section 3.4).

### 4.1 What a cycle model is

A 0-D *cycle model* represents the engine as a chain of thermodynamic components—inlet, fan, compressors, combustor, turbines, nozzles—each transforming the air’s pressure, temperature and composition according to its governing equations, without resolving any internal geometry. Each turbomachine carries a *component map*: a table, obtained from rig tests or scaled from a similar machine, giving its efficiency and flow as a function of rotational speed and operating point. The model runs in two modes:

**Design mode** sizes the engine: given targets (thrust, component pressure ratios, turbine inlet temperature), it computes the flow areas, map scale factors and shaft-work balance that a machine meeting those targets must have.

**Off-design mode** answers the service question: given the now-fixed geometry, what does the engine do at any other flight condition and thrust setting? This is the mode the EHM baseline decks and the influence coefficient matrix are built from.

pyCycle solves both modes with a Newton solver: it iterates on a set of unknowns (mass flow, fuel-air ratio, spool speeds, map operating points) until a set of residual equations (nozzle-area match, shaft power balance, thrust target) is driven to zero. Newton solvers are powerful but fragile far from a good initial guess—a fragility that shaped several decisions below.

### 4.2 Strategy: adapt, don’t build from scratch

pyCycle ships a validated example of a two-spool, separate-flow, cooled high-bypass turbofan (`high_bypass_turbofan.py`) with the full component graph, the turbine-cooling bleed network,

shaft balances and off-design solver wiring already working. Building the CFM56 from a blank file would re-derive all of that plumbing and typically dies in Newton divergence. Instead, a *morphing* protocol is adopted: the example is vendored into the repository as a known-good regression reference, and the model is steered toward the CFM56-7B26 by changing **at most three parameters per step**, requiring convergence at every step before the next. Every converged step is a commit; if a step diverges, the change is bisected.

All design decisions were fixed in writing *before* coding (`docs/f1-model-spec.md`): the -7B26 variant; tabular thermodynamics for speed with a CEA cross-check planned (CEA is NASA’s chemical-equilibrium code —more accurate, roughly an order of magnitude slower); the design point at cruise, Mach 0.78 / 35 000 ft / ISA (the “aerodynamic design point” convention: an engine is designed for cruise, where it spends most of its life, and takeoff is an off-design condition); pyCycle’s generic component maps, scaled —no public CFM56 maps exist, a declared limitation; thrust set through corrected N1 in off-design (the -7B is an N1-rated engine); pyCycle-native units inside the model with SI only at the boundary; and a table of anticipated solver failure modes, each with a planned countermeasure —one of which proved prophetic (Section 4.4.3).

### 4.3 Design point (WP1.1)

The cycle graph comprises: flight conditions, inlet, fan, flow splitter, booster, HPC with three bleed ports (HPT vane and blade cooling, customer bleed), a post-compressor bleed feeding the LPT, combustor, cooled HPT and LPT, ducts with pressure losses, convergent core and bypass nozzles, the two shafts, and an accessory power extraction of 250 hp on the HP shaft (driving the aircraft’s generators and pumps). In design mode, four implicit balances close the cycle: the inlet mass flow  $W$  meets the thrust target; the fuel–air ratio (FAR) meets the target turbine inlet temperature  $T_{t4}$ ; and the HPT and LPT expansion ratios zero the net power on each shaft (each turbine produces exactly what its compressors and losses consume).

Table 4.1: Design-point results (Mach 0.78, 35 000 ft, ISA). Auto-generated from the model.

| Quantity                     | Value at the design point |
|------------------------------|---------------------------|
| Net thrust $F_n$             | 24.38 kN (5480 lbf)       |
| TSFC                         | 0.6214 lb/(lbf·h)         |
| Bypass ratio (BPR)           | 5.10                      |
| Overall pressure ratio (OPR) | 30.03                     |
| $T_{t4}$                     | 1587 K (2857 °R)          |
| Inlet mass flow $W$          | 142.0 kg s <sup>−1</sup>  |
| Fuel–air ratio (FAR)         | 0.0251                    |
| HPT expansion ratio          | 3.586                     |
| LPT expansion ratio          | 4.288                     |
| Total cooling/bleed fraction | 0.239                     |

Table 4.2: Total conditions at each gas-path station at the design point. Auto-generated.

| Station | Location    | $P_t$ [bar] | $T_t$ [K] |
|---------|-------------|-------------|-----------|
| 2       | Fan inlet   | 0.358       | 245.5     |
| 21      | Fan exit    | 0.603       | 289.5     |
| 25      | HPC inlet   | 1.149       | 354.2     |
| 3       | HPC exit    | 10.739      | 703.9     |
| 4       | Burner exit | 10.159      | 1587.2    |
| 45      | HPT exit    | 2.833       | 1141.6    |
| 5       | LPT exit    | 0.657       | 806.3     |




Figure 4.1: Total pressure and temperature along the gas path at the design point. Compression peaks at station 3 ( $\sim 11$  bar, Table 4.2), heat addition at station 4, and work extraction across stations 45 and 5.

The design point converges with a Newton residual below  $10^{-6}$  and satisfies all five acceptance windows defined a priori: BPR  $5.10 \pm 0.2$  (the EEDB target), OPR within its window,  $T_{t4}$  within a plausible band, total cooling-plus-bleed fraction between 18 and 25 % of core flow, and thrust exactly on target (Table 4.1). The resulting TSFC ( $\approx 0.62$  lb/(lbf-h)) lands within 2 % of the publicly quoted cruise value for this engine *without having been used as a calibration target* —an encouraging consistency check.

## 4.4 Calibration against measured data (WP1.2)

### 4.4.1 Data sources and philosophy

Off-design calibration uses exclusively **measured, certified data** (Table 2.1). The TCDS provides limits and rated thrusts. The ICAO Engine Emissions Databank provides something less well known: sea-level test-bed *measured fuel flows* at the four landing-takeoff-cycle thrust settings (100, 85, 30 and 7 % of rated thrust  $F_{00}$ ), plus the engine pressure ratio at rated output (27.61) —all for the exact -7B26 variant, traceable to certification testing, and free. Most academic engine models ignore this source.

The anchor points are solved *thrust-matched*: the fuel–air ratio balance is set to hold  $F_n = PC \cdot F_{00}$  (PC being the power fraction). The model’s fuel flow at each anchor is therefore a genuine **prediction** confronted with the EEDB measurement —not a quantity fitted to it.

### 4.4.2 Calibration iterations

The first run (model freshly adapted from the example, not yet calibrated to the SLS data) already predicted takeoff fuel flow within  $-2.1$  %, but showed two quantitative defects:

1. **N2 above its redline at rated thrust:** 15 311 rpm against the certified limit of 15 183 rpm. Cause: the reference speed used to scale the generic HPC map —the map’s speed-versus-flow shape is not the real compressor’s, so the speed labels it implies must be anchored

deliberately. Fix: HP-shaft design reference from 14 324 to 13 940 rpm, placing rated-thrust N2 at 14 915 rpm ( $\approx 103\%$ ), inside the limit.

2. **Takeoff pressure ratio 28.99 versus the measured 27.61 (+5.0 %)**. Fix: HPC design pressure ratio from 9.81 to 9.35. The measured value takes precedence over the initial derived estimate, and the cruise OPR becomes a consequence ( $\approx 30$ ).

Table 4.3: SLS anchors versus the ICAO databank measurements after calibration.  $W_f$  model is the model’s prediction at imposed thrust. Auto-generated.

| Anchor      | $\%F_{00}$ | $F_n$ [kN] | $W_f$ model | $W_f$ EEDB | error [%] | tol. [%] | gated |
|-------------|------------|------------|-------------|------------|-----------|----------|-------|
| A2 Takeoff  | 100        | 117.0      | 1.204       | 1.221      | -1.40     | 3.0      | ✓     |
| A3 Climbout | 85         | 99.4       | 0.977       | 0.999      | -2.23     | 3.0      | ✓     |
| A4 Approach | 30         | 35.1       | 0.328       | 0.338      | -3.08     | 5.0      | ✓     |
| A5 Idle     | 7          | 8.2        | 0.125       | 0.113      | +10.57    | 5.0      | —     |




Figure 4.2: Fuel-flow prediction error at each anchor against the EEDB measurement. Gray bands are the contract tolerances ( $\pm 3\%$  at takeoff and climb-out,  $\pm 5\%$  at approach and idle); the hollow marker (idle) converges but sits outside tolerance and is reported without blocking the milestone (Section 4.4.3).

After both corrections (Table 4.3 and Figs. 4.2 and 4.3), the three gated anchors meet their tolerances: takeoff at  $-1.40\%$  fuel-flow error with the pressure ratio within  $+0.3\%$  of the measured value and both shaft speeds inside their redlines; climb-out at  $-2.23\%$ ; approach at  $-3.08\%$ .

#### 4.4.3 Idle convergence: diagnosis and cure

The idle point (7% of  $F_{00}$ , static) systematically diverges from a cold start. At such low power the nozzle pressure ratios approach unity —the exhaust barely pushes— and the nozzles’ internal static-pressure sub-solver bounces against its lower bound, leaving the global Newton iteration without a descent direction. Worse, the failed attempt leaves the point’s internal states (flow stations, map positions) corrupted, so re-seeding only the balance variables does not rescue it: the idle point must *never* start cold at its final setting. The cure —anticipated as a generic countermeasure in the specification— is **power continuation**: the point starts at 30% of  $F_{00}$  (where it converges from cold, just like the approach anchor) and walks down warm through  $0.30 \rightarrow 0.20 \rightarrow 0.14 \rightarrow 0.10 \rightarrow 0.08 \rightarrow 0.07$ , re-solving at each step. The logic is encapsulated in the library (`solve_anchors()`) and covered by the tests.




Figure 4.3: The model’s sea-level-static working line (a continuous sweep of thrust setting) against the four measured ICAO databank points. The curvature at low power reflects the degraded accuracy of generic maps far from their scaling point.

With continuation, idle converges and predicts fuel flow with +10.6% error. This is deep map-extrapolation territory —the generic map’s speed-flow shape at very low power is not the real compressor’s— a known limitation of the approach; the anchor is **reported but not gated** for milestone H1, a decision recorded in the calibration contract (`gated:~false`).

## 4.5 Baseline decks (WP1.3)

Both EHM pipelines need a *baseline*: what a healthy engine reads at any operating condition, so that measured values can be turned into deviations. The baseline is produced by sweeping the healthy model over a realistic flight envelope —altitude blocks with their plausible Mach ranges (no Mach 0.8 at sea level), ambient temperature offsets of 0, +15 and +30 °C above ISA, and six thrust settings from 50 to 100% of the locally available maximum. The 50% floor is deliberate: airline EHM trending consumes takeoff, climb and stable-cruise reports, all high-power conditions; approach and idle are neither trending conditions nor reliable model territory (Section 4.4.3). At each condition the model first finds the maximum thrust available at the rating temperature (point `OD_max`, throttled by  $T_4$ ), then solves the part-power point at the commanded fraction (`OD_pt`) —the same two-point pattern used by the pyCycle reference example. The rating temperature is fixed at  $T_{4,\max} = 3200^\circ\text{R}$ , a rounded envelope constant chosen from the calibrated takeoff anchor (imposing the certified rated thrust at SLS required  $T_4 \approx 3175^\circ\text{R}$ , Table 4.3); a real FADEC modulates its rating limits across the envelope, so this constant is a declared simplification —adequate here because the baseline uses *fractions* of the local maximum, not its absolute value.

Two engineering lessons from WP1.2 shaped the sweep. First, the walk is ordered for warm starting within each block (thrust descending), and the independent (altitude, Mach) blocks run in *parallel processes*, one Problem per worker (project norm N1: long decomposable computations are parallelized; the sweep takes 3.5 minutes on all cores versus 10 minutes serial). Second —the lesson learned the hard way— a failed Newton attempt corrupts the point’s internal states beyond re-seeding, so the recovery action on any failure is to *rebuild* the problem cold with altitude-appropriate guesses (norm N2); a first version of the sweep without this recovery lost every point downstream of the first divergence.

The result is stored as a table plus a scattered linear interpolator (Delaunay triangulation with

barycentric interpolation, SciPy’s `LinearNDInterpolator`) in the four operating coordinates, and its quality is measured by leave-one-out cross-validation: each grid point is removed, predicted from all the others, and the relative error recorded — Table 4.5 reports the per-channel median, 95th percentile and maximum. Median errors are a few tenths of a percent; the tail percentiles are dominated by envelope-corner points whose interpolation simplices span across altitude blocks in raw physical coordinates.

#### 4.5.1 Corrected-parameter exponents and the corrected-space baseline

The fix for those tails is the one anticipated in Section 2.3: build the baseline in *corrected-parameter* space. The correction exponents are fitted on the deck itself rather than copied from generic tables: per channel  $Y$ , a linear least-squares fit of

$$\log Y = \underbrace{\sum_{k=0}^3 c_k (\log N1_c)^k}_{\text{power line}} + a \log \theta + b \log \delta, \quad (4.1)$$

where the cubic polynomial absorbs the dependence on the corrected speed (the “power line”) and the exponents  $(a, b)$  capture whatever ambient dependence remains — exactly the quantities the correction  $Y_{\text{corr}} = Y/(\theta^a \delta^b)$  then removes. The fitted exponents land squarely on their textbook values without having been told them (Table 4.4): fuel flow  $a = 0.63$ ,  $b = 1.02$  (handbooks quote  $\theta^{0.5-0.7} \delta$ ); N2  $a = 0.49$ ,  $b \approx 0$  (the  $\sqrt{\theta}$  corrected-speed law); EGT  $a = 0.95$ ,  $b \approx 0$  (temperature ratio). This is a further independent consistency check of the model physics.

Re-running the leave-one-out audit on the corrected channels over (corrected N1, Mach) collapses the tails by an order of magnitude (Table 4.4): worst-case N2 error drops from 9.7 % to 0.5 %, EGT from 24 % to 2.0 %, fuel flow from 91 % to 6.6 %. Two remarks for honesty: net thrust is excluded — it is not an EHM sensor channel (it comes from the thrust-setting definition), and it does not collapse under a  $\theta/\delta$  law at fixed N1c because of its strong direct Mach dependence; and the residual corrected-space errors are comparable to the sensor noise floor that phase F2 will inject ( $\sigma_{\text{EGT}} \approx 0.3$  %,  $\sigma_{W_f} \approx 0.5$  %). Baseline error is also common-mode: both EHM pipelines consume the same baseline, so it does not bias the comparison.

Table 4.4: Fitted correction exponents per channel and the leave-one-out error before (raw 4-D coordinates) versus after (corrected space). Auto-generated.

| Channel   | $a$ ( $\theta$ ) | $b$ ( $\delta$ ) | raw LOO P95/max [%] | corrected LOO P95/max [%] |
|-----------|------------------|------------------|---------------------|---------------------------|
| Fuel flow | 0.628            | 1.022            | 15.77 / 90.6        | 3.08 / 6.6                |
| N2        | 0.495            | 0.007            | 2.65 / 9.7          | 0.34 / 0.5                |
| EGT       | 0.949            | 0.002            | 6.01 / 24.1         | 1.12 / 2.0                |

Table 4.5: Leave-one-out interpolation error of the baseline deck, per channel. Auto-generated.

| Channel    | Median [%] | P95 [%] | Max [%] |
|------------|------------|---------|---------|
| Fuel flow  | 0.498      | 15.767  | 90.603  |
| N1         | 0.268      | 6.369   | 25.721  |
| N2         | 0.080      | 2.649   | 9.697   |
| EGT        | 0.167      | 6.012   | 24.062  |
| Net thrust | 0.000      | 16.437  | 85.402  |

## 4.6 Influence coefficient matrix and observability (WP1.4)

### 4.6.1 Health-parameter injection

To compute the ICM —and, in phase F2, to simulate degraded engines— the model must accept imposed health deviations. `pyCycle` scales its generic component maps with per-component design scalars (efficiency and flow); the off-design points normally inherit them from the design point. In the `MPCFM56Study` model those connections are routed through multiplier components, so that any efficiency or flow-capacity deviation can be dialed in per run. Two implementation subtleties are worth recording: (i) the multipliers must execute *before* the off-design point —the multi-point group runs its children in insertion order, and a mis-ordered version silently solved the off-design point with unscaled maps; the symptom (a “healthy” point that did not reproduce the design point) was caught by the self-consistency check below; and (ii) holding N1 constant, the CFM56’s rating parameter, requires a fuel-flow balance targeting the LP spool speed through a passthrough component, since the speed is itself the output of another balance.

The wiring is validated by a self-consistency property that is now a permanent test: the *healthy* off-design point at cruise with N1 equal to its design value must reproduce the design point exactly. It does: thrust 5480.0 lbf, N2 13 940.0 rpm, OPR 30.03, EGT 1141.6 K —machine-precision agreement with Table 4.1.

### 4.6.2 The ICM at the reference conditions

The ICM is computed by central finite differences ( $\pm 0.5\%$  per health parameter) at the two conditions where airline EHM snapshots are taken: cruise (M 0.78/35 000 ft) and sea-level takeoff, at constant N1. Figure 4.4 shows the cruise matrix for the extended sensor set; every sign satisfies the physical expectations (e.g. a healthier HPT runs cooler and thriftier: negative EGT and  $W_f$  entries in its efficiency column), and these sign checks run automatically in the test suite.




Figure 4.4: Influence coefficient matrix at cruise (extended sensor set): % change of each measured channel per +1 % change of each health parameter. Auto-generated from the model.

### 4.6.3 Observability: the quantitative case for hypothesis H2

With the cockpit set only (N2,  $W_f$ , EGT —N1 is the held rating parameter, so it carries no information), the ICM has rank 3 for 10 unknowns and the geometry of its columns is damning: the minimum angle between fault signatures is **1.3 degrees**, with seven pairs below 15 degrees



(Table 4.7). The most confusable pair, HPC efficiency versus HPT efficiency, is precisely the classical HPC/HPT ambiguity reported in the GPA literature [9] —here quantified for this engine. Two faults whose signatures differ by 1.3 degrees are, at realistic noise levels, indistinguishable to any linear estimator: this is the smearing mechanism measured, and it defines the “confusable” subset on which hypothesis H2 will compare the AI’s isolation ability against WLS-GPA. The extended sensor set (adding P25/T25/PS3/T3) raises the rank to 7 and multiplies the minimum angle by roughly five —the quantitative basis for the sensor-set ablation of contribution C6.

The analysis is repeated over a six-point grid spanning the envelope —both snapshot conditions plus power, altitude, climb and hot-day variations (Table 4.6). The observability structure barely moves: the minimum cockpit signature angle stays between 1.2 and 1.4 degrees and the confusable-pair count is constant at seven. The smearing problem is therefore *intrinsic to the cockpit sensor set*, not an artifact of one flight condition —which both justifies interpolating the ICM over this grid in phase F3 and forecloses the easy escape of “diagnose somewhere else in the envelope”.

Table 4.6: Observability of the cockpit ICM across the operating-point grid. Auto-generated.

| Operating point     | cond. | $\alpha_{\min}$ ckpt. [deg] | pairs | $\alpha_{\min}$ ext. [deg] |
|---------------------|-------|-----------------------------|-------|----------------------------|
| Cruise M0.78/FL350  | 12.2  | 1.32                        | 7     | 8.62                       |
| Cruise, low power   | 13.0  | 1.20                        | 7     | 6.68                       |
| Cruise FL390        | 11.3  | 1.37                        | 7     | 8.60                       |
| Climb 10 kft/M0.4   | 12.6  | 1.35                        | 7     | 7.38                       |
| Takeoff SLS         | 10.5  | 1.33                        | 7     | 7.92                       |
| Takeoff SLS, ISA+30 | 11.4  | 1.25                        | 7     | 8.97                       |

Table 4.7: Confusable fault pairs at cruise with cockpit sensors (signature angle  $< 15^\circ$ ). Auto-generated.

| Fault A               | Fault B               | Angle [deg] |
|-----------------------|-----------------------|-------------|
| $\eta_{\text{HPC}}$   | $\eta_{\text{HPT}}$   | 1.32        |
| $\eta_{\text{FAN}}$   | $\eta_{\text{LPT}}$   | 4.32        |
| $\eta_{\text{HPT}}$   | $\Gamma_{\text{HPT}}$ | 6.02        |
| $\Gamma_{\text{FAN}}$ | $\eta_{\text{LPT}}$   | 6.52        |
| $\eta_{\text{HPC}}$   | $\Gamma_{\text{HPT}}$ | 7.20        |
| $\eta_{\text{FAN}}$   | $\Gamma_{\text{FAN}}$ | 10.05       |
| $\eta_{\text{FAN}}$   | $\eta_{\text{LPC}}$   | 13.53       |

#### 4.6.4 Thermodynamics cross-check

Decision D2 (tabular thermodynamics for speed) is closed by re-solving the design point with NASA’s chemical-equilibrium code (CEA): all key quantities agree within 0.7% (Table 4.8), an order of magnitude below the  $\pm 3\%$  calibration tolerance. Tabular thermodynamics is therefore retained for all fleet-scale computation.

## 4.7 Declared limitations

The model is *representative*, not certifiable, and its limits are declared for citation in the results chapters: (i) no transients —steady-state points only; (ii) variable geometry (bleed valves, variable stators) implicit in the maps, not modeled; (iii) no Reynolds or humidity corrections; (iv) absolute N1/N2 labels approximate by construction (generic map shapes), though respecting the certified redlines at the rated point; (v) the model’s EGT is the HPT-exit temperature (station 45), a consistent proxy —identical for ground truth and for both EHM pipelines— of the

Table 4.8: Design point solved with tabular versus CEA thermodynamics. Auto-generated.

| Quantity                | Tabular   | CEA       | $\Delta$ [%] |
|-------------------------|-----------|-----------|--------------|
| Net thrust [lbf]        | 5480.0000 | 5480.0000 | -0.000       |
| TSFC [lb/(lbf·h)]       | 0.6214    | 0.6249    | +0.553       |
| Inlet mass flow [lbm/s] | 313.0851  | 315.2029  | +0.676       |
| Fuel-air ratio          | 0.0251    | 0.0250    | -0.122       |
| HPT expansion ratio     | 3.5865    | 3.5902    | +0.104       |
| LPT expansion ratio     | 4.2879    | 4.3109    | +0.537       |

certified T49.5, whose displayed value additionally carries the shunt and trim functions described in Section 2.2; and (vi) the idle error quoted above. None of these limitations affects the validity of the AI-versus-traditional comparison, which rests on the model’s sensitivity structure (the ICM), not on its absolute values.

## 4.8 Automated verification

The chapter’s claims are pinned by tests: design-point convergence and acceptance windows; convergence of all four anchors including the idle continuation; fuel-flow and pressure-ratio tolerances at the gated anchors; N1/N2 redlines at rated thrust; the Study self-consistency property (healthy off-design = design); the ICM physical sign checks and its rank-3 cockpit underdetermination; and the pyCycle environment smoke test. Twelve tests green in continuous integration at the time of writing.

## Chapter 5

# The synthetic fleet: SynCFM56

*This chapter in brief: one hundred virtual engines live full lives — fouling, washes, wear, the occasional bird strike and sensor drift — while the generator records both what an airline would see and the hidden truth. Three audits gate the result; one failed on first pass and forced a redesign, told here in full.*

This chapter documents phase F2: the generator that turns the F1 twin into a 100-engine run-to-failure fleet with complete ground truth, the audits that gate it (one of which failed on first pass and forced a design change — documented in full in Section 5.4), and the declaration of milestone H2.

### 5.1 Generator architecture: linearize, then audit

A fleet of 100 engines flying  $\sim 16\,000$  cycles each, two snapshots per flight, would require over three million full pyCycle solves per fleet realization — unusable for iteration. Instead, the generator exploits exactly what F1 built: every snapshot is produced by the linearization

$$z(u, \mathbf{x}) = z_0(u) (1 + \mathbf{H}(u) \mathbf{x} / 100), \quad (5.1)$$

where  $z_0(u)$  is the healthy baseline and  $\mathbf{H}(u)$  the influence coefficient matrix, both linearly interpolated between the ICM grid points that bracket the sampled operating condition (takeoff snapshots: in  $\Delta T_{ISA}$ ; cruise snapshots: in commanded N1). N1 itself carries zero deviation by construction — it is the held power-setting parameter, not a health channel. The whole fleet generates in 37 seconds on all cores (one worker process per engine, norm N1), with per-engine deterministic random seeds so the output is reproducible regardless of process scheduling.

Two properties of this choice must be kept distinct. First, the dataset is *self-consistent by construction*: the recorded ground truth  $\mathbf{x}$  is exactly the state that generated the measurements, so estimator evaluations against truth are exact regardless of any linearization error. Second, *fidelity to the full nonlinear physics* is an empirical question — which is why the first gate audit re-solves full pyCycle at states sampled from the generated fleet (Section 5.4.1).

### 5.2 Ground-truth trajectories

Each engine draws a degradation “personality” from the fault catalog (`conf/fault_catalog.yaml`, the versioned contract): a log-normal severity multiplier per mechanism, a wash schedule, Poisson-arriving foreign-object damage, optional sensor drifts, and —in roughly half the fleet— one *acute fault episode* (Section 5.4.2 explains why these exist). The mechanisms follow the physical profiles of Table 2.2: saturating-exponential fouling, slow linear erosion, bilinear break-in of tip clearances, linearly accelerating hot-section deterioration.

Two implementation details worth recording:

- **Wash sawtooth, exact.** Between washes the fouling level relaxes exponentially toward its asymptote; each wash multiplies the current level by  $(1 - r)$  with recovery  $r$  drawn per event. The trajectory is computed segment-wise with the exact exponential solution. A tempting shortcut — permanently subtracting the removed amount — was implemented first and rejected: it makes the trajectory approach asymptote — removed and under-predicts late-life fouling.
- **Composability of truth.** The generator stores not only the total  $\mathbf{x}(n)$  but each mechanism’s separate contribution, so any later analysis can ask not just “how degraded” but “degraded by *what*”.

End of life is declared when the EGT margin at the hot-day takeoff reference reaches zero, with the margin computed by projecting  $\mathbf{x}(n)$  through the takeoff-hot ICM’s EGT row — the same linearization as the snapshots. New-engine margins are drawn per engine ( $85 \pm 6^\circ\text{C}$ ). Figure 5.1 shows the resulting fleet behavior: the canonical fast-early / slow-late erosion with wash sawtooth, and lives spanning 10 500–20 700 cycles.




Figure 5.1: EGT-margin trajectories of five engines. Wash events produce the sawtooth recoveries; engine-to-engine spread comes from the hierarchical severity multipliers and the drawn new-engine margins. End of life is the zero crossing. Auto-generated from the fleet.

### 5.3 Snapshots and the measurement model

Each flight cycle emits two reports, mimicking airline ACARS practice: a takeoff snapshot (sea level, ambient offset drawn from a climate distribution) and a cruise snapshot (FL350/M0.78, commanded N1 drawn per flight). Truth channels pass through the sensor model of the catalog: per-channel Gaussian noise (absolute or percentage  $\sigma$ ), quantization to the recording resolution, additive drift ramps on the affected engines (37 of 100 — matching the catalog’s per-sensor probabilities summing to 0.36), and missing data as isolated losses plus ACARS outage bursts (4.1 % of snapshots). Every row carries, alongside the measured values: the true channel values, the full ground-truth health vector, the EGT margin, the remaining useful life, the isolation label, and drift flags. Table 5.1 summarizes the frozen dataset.




Figure 5.2: Ground-truth health parameters of one engine with an acute fault episode (dashed marker). Vertical gray lines are washes (visible as sawtooth in the HPC traces); the hot-section traces show the monotone efficiency loss and flow-capacity opening. Auto-generated.

Table 5.1: SynCFM56 v1.0 at a glance. Auto-generated from the fleet artifacts.

| Property                                                           | Value                        |
|--------------------------------------------------------------------|------------------------------|
| Engines (train / val / test)                                       | 100 (70 / 10 / 20)           |
| Snapshot rows (takeoff + cruise per flight)                        | 1 584 808                    |
| Life [cycles]: median (min-max)                                    | 15442 (10515–20738)          |
| Censored engines                                                   | 0                            |
| Engines with an acute fault episode                                | 49 (all 6 target parameters) |
| Engines with a sensor drift                                        | 37                           |
| Wash EGTM recovery: mean, frac. positive                           | 2.8 °C, 99.8 %               |
| End-of-life $\Delta EGT$ / $\Delta W_f$ (all engines correct sign) | +68 K / +5.8 %               |
| Measured-noise residual vs. catalog (EGT)                          | 2.51 K vs. 2.5 K             |

## 5.4 Gate audits — including the one that failed

### 5.4.1 Nonlinearity of the generator

Eighty health states were sampled from the generated fleet (stratified by life fraction, half from the last 30 % of life where deviations are largest) and re-solved with full pyCycle at the exact ICM grid conditions, so the comparison isolates nonlinearity from interpolation. Table 5.2 reports the per-channel error of Eq. (5.1) against the full solution, next to the sensor noise it must be judged against: medians of 0.01–0.33 %, tails (P95) at or below 1 %, concentrated at end of life. Combined with the self-consistency property of Section 5.1, the linearization is adequate: the residual infidelity to full physics is at the noise floor, identical for both EHM pipelines, and irrelevant to truth-referenced scoring.

Table 5.2: Nonlinearity audit: linear generator versus full pyCycle solves at fleet-sampled health states. Auto-generated.

| Condition        | Channel | median [%] | P95 [%] | max [%] | noise $\sigma$ [%] |
|------------------|---------|------------|---------|---------|--------------------|
| Cruise           | N2      | 0.012      | 0.035   | 0.038   | 0.05               |
| Cruise           | $W_f$   | 0.215      | 0.602   | 0.785   | 0.50               |
| Cruise           | EGT     | 0.329      | 0.981   | 1.073   | 0.21               |
| Takeoff, hot day | N2      | 0.037      | 0.085   | 0.089   | 0.05               |
| Takeoff, hot day | $W_f$   | 0.139      | 0.429   | 0.479   | 0.50               |
| Takeoff, hot day | EGT     | 0.257      | 0.843   | 0.959   | 0.18               |

### 5.4.2 Difficulty: the audit that failed, and what it taught

The difficulty gate is designed to prevent a trivially easy dataset from flattering the AI: a deliberately weak classifier (multinomial logistic regression on the 16 raw measured channels) must *not* solve the isolation task; the pre-set threshold is 60 % accuracy.

**First pass: failed.** With the original labeling — the dominant *chronic* mechanism per snapshot — the trivial classifier scored **81.6 %** (majority-class baseline 54.6 %). Root-cause analysis: chronic mechanisms co-evolve with age in *every* engine (fouling saturates early, hot-section deterioration accumulates late), so the chronic label is largely an *age proxy*, and raw absolute channel levels encode age directly. The task the label defined was not fault isolation at all. Two responses were possible: relax the threshold (cosmetic) or fix the design (structural). The structural fix was taken.

**Design change: acute fault episodes.** What hypothesis H2 actually tests is the isolation of *localized faults with overlapping signatures* — the regime where the ICM observability analysis proved cockpit sensors nearly blind (minimum signature angle 1.3°, Table 4.7). The catalog therefore gained discrete *single-parameter* fault episodes: a fast ramp (50–500 cycles) to a sustained magnitude on one health parameter, drawn from six targets that deliberately include the confusable pairs ( $\eta_{HPC}$  vs.  $\eta_{HPT}$ ,  $\eta_{HPT}$  vs.  $\Gamma_{HPT}$ ), injected in  $\sim 50$  % of engines at a random point of their lives. The gated task became: classify each snapshot as *no acute fault* or by the faulted parameter — a 7-class isolation problem.

**The audit also caught a generator bug.** The first acute implementation drew the episode onset as a fraction of the *maximum simulation horizon* (30 000 cycles) rather than of the engine’s actual life ( $\sim 16$  000): most episodes landed beyond end of life and only 15/100 engines showed one. The fix computes a chronic-only provisional life first, then places the onset as a fraction of it (two-pass generation); the final fleet has 49/100 acute engines with all six target parameters represented.

**Second pass: passed.** On the corrected fleet the trivial classifier achieves **54.0 %** accuracy (macro-F1 0.30) on the gated isolation task — under the 60 % threshold, exactly as the signature-

angle physics predicts (Table 5.3). The chronic-mechanism label is retained in the dataset and reported as a secondary, explicitly-not-gated metric (81.6 % accuracy — high, expected, and uninformative about isolation ability). The episode is recorded here in full because it is evidence the gates are real: a pre-registered criterion failed, the failure was diagnosed to a design flaw rather than argued away, and the fix strengthened the benchmark.

Table 5.3: Difficulty audit on the final fleet (trivial classifier: multinomial logistic on raw measured channels). Auto-generated.

| Trivial-classifier task                        | Accuracy [%] | macro-F1 | Gate [%] | Verdict  |
|------------------------------------------------|--------------|----------|----------|----------|
| Acute-fault isolation (gated, 7 classes)       | 54.0         | 0.299    | < 60     | PASS     |
| Chronic-mechanism label (secondary, age proxy) | 80.1         | 0.607    | —        | reported |

### 5.4.3 Realism

Quantitative checks of macroscopic behavior, all in Table 5.1: the wash sawtooth is visible (mean EGTM recovery  $+2.8^{\circ}\text{C}$ , positive at 99.75 % of the 400 sampled wash events); end-of-life deviations carry the physical deterioration signature in 100 % of engines ( $\Delta\text{EGT} +68\text{ K}$ ,  $\Delta W_f +5.7\%$ ); the measured-noise residual on drift-free engines reproduces the catalog  $\sigma$  (2.51 vs. 2.50 K); lives center on 15 400 cycles with a realistic severe-degrader tail and no censored engines.

## 5.5 Milestone H2: declared closed

All gate criteria are met: realism and difficulty audits passed (the latter after the documented design change), nonlinearity quantified at the noise floor, split-by-engine leakage checks automated in CI, and the dataset datasheet written (`docs/syncfm56-datasheet.md`). SynCFM56 v1.0 is frozen: regeneration is deterministic from the catalog and seed, so the dataset is fully specified by the repository state. Known limitations, declared for downstream chapters: linearized generation (audited, Table 5.2); two fixed snapshot conditions with ambient/power scatter rather than a full mission mix; chronic labels are age-correlated by nature; and one acute episode per engine at most.

## Chapter 6

# The traditional EHM pipeline

*This chapter in brief: the classical monitoring stack —smoothed deviations, statistical alarms, Kalman health tracking, expert isolation rules, margin extrapolation— is built with care and run on the test fleet. Its characteristic strengths and weaknesses, known from the literature, now appear as measured numbers against ground truth: fast detection of strong faults, heavy smearing on confusable ones, optimistic early-life prognosis. Two detector-design lessons learned along the way are recorded. Nothing here is tuned yet: that happens under the symmetric budget of phase F5.*

### 6.1 Pipeline overview

The traditional pipeline mirrors the industrial monitoring stack (SAGE/ADEM-class systems). Per engine and per flight, the cruise snapshot is converted into corrected-space percentage deviations against the published baseline (the same F1 artifacts available to both EHM families); the deviations feed four consumers:

1. **Smoothing** (Holt double exponential, level + trend): the airline-facing trend plots, and the source of *innovations* — one-step forecast errors, which are the correct series for event detection because the chronic trend has been absorbed by the level and trend states.
2. **Detection**: a CUSUM on the innovations (catches steps: FOD, abrupt faults) combined with a dual-EWMA *gap* detector — fast EWMA minus slow EWMA — whose gap opens by roughly the fault magnitude during a ramp (catches acute episodes). Alarms require persistence ( $k$ -of- $n$ ) and, for EGT, are one-sided: washes pull the deviation down, and improvement is not a fault.
3. **Health estimation**: snapshot WLS-GPA (Eq. (2.4)) and a random-walk Kalman-GPA tracker (Eq. (2.5)) with the operating-point-interpolated ICM. The tracker is *wash-aware*: at logged wash events (maintenance records are available to a real EHM system too) the recoverable compressor states are pulled toward zero and their covariance reopened.
4. **Isolation and prognosis**: on detection, the deviation step across the alarm is matched against the single-parameter ICM signatures (nearest-cosine expert rule); the remaining useful life comes from a robust Theil–Sen extrapolation of the tracked takeoff EGT margin to zero, with a NASA-style horizon cap.

### 6.2 Two detector-design lessons

Both are classical results rediscovered the honest way — by watching the first implementation fail — and both are now embodied in tests:



- **CUSUM on the raw deviation is wrong for aging systems.** The first run applied CUSUM to the EGT deviation itself: the chronic trend integrates without bound, so *every* engine alarmed mid-life (detection recall 0, every healthy engine a false alarm). Step detectors belong on innovations, where the expected value under chronic aging is zero.
- **A Holt trend-shift detector cannot see acute ramps.** At realistic smoothing gains the noise of the estimated trend exceeds the slope added by a 50–500-cycle ramp entirely. The dual-EWMA gap detector solves this: over the ramp the fast average follows and the slow one lags, opening a gap of the order of the full fault magnitude — signal-to-noise an order of magnitude better than the trend estimate.

### 6.3 Results on the test fleet (v0 defaults)

Table 6.1 shows the pipeline’s scores on the 20 test engines with its engineering-default settings — deliberately untuned, since hypothesis testing requires the tuning budget to be spent symmetrically on both families (F5). Three patterns, each anticipated by the literature and by the ICM geometry, are now measurements:

Table 6.1: Traditional pipeline on the test split, v0 defaults. Auto-generated.

| Metric (test split, v0 defaults)              | Value        |
|-----------------------------------------------|--------------|
| Detection recall (acute episodes)             | 0.50         |
| Median detection delay                        | 98 cycles    |
| False-alarm engines (no acute episode)        | 3 / 10       |
| Isolation accuracy (detected episodes)        | 0.40         |
| Isolation accuracy, confusable subset         | 0.00 (n=2)   |
| Kalman health RMSE (median, 2nd half of life) | 0.42 %       |
| Smearing index (median, acute engines)        | 0.85         |
| RUL median error at 50 % of life              | +7612 cycles |
| RUL median error at 70 % of life              | +3279 cycles |
| RUL median error at 90 % of life              | +1903 cycles |

**Detection is fast but partial.** Detected episodes alarm within  $\sim 100$  cycles (against ramps of 50–500), but recall is 0.5: the missed episodes are dominated by the weak-signature faults ( $\Gamma_{\text{HPT}}$  moves EGT by only +0.11 % per percent — half a noise standard deviation) and by drift-contaminated engines.

**Isolation collapses exactly where the ICM said it would.** Overall isolation is 40 %; on the confusable subset it is 0 %. Figure 6.1 shows the mechanism live: the Kalman tracker follows the *measurements* faithfully but splits the acute step between the faulted parameter and its  $1.3^\circ$  partner — the smearing index says 85 % of the estimated magnitude lands on healthy components. The estimator is not broken; the information is not in three cockpit channels.

**Margin extrapolation is optimistic early.** Figure 6.2: at half-life the median RUL error is +7600 cycles, shrinking to +1900 at 90 % of life. Linear extrapolation under accelerating degradation is systematically late to predict retirement — the funnel closes only near the end, which is precisely when the prediction is least useful.

### 6.4 Milestone H3

The gate requires the traditional pipeline to run end-to-end on the test fleet and produce the common metric set — met above ( $\sim 2$  minutes per fleet, one worker per engine). Its defaults




Figure 6.1: Smearing, live: Kalman-GPA on a test engine with an acute fault (onset dashed). The tracker reacts, but divides the step between the faulted parameter and its confusable partner. Auto-generated.




Figure 6.2: RUL error of the margin-extrapolation prognosis versus the moment of prediction (test engines). Positive = late prediction. Auto-generated.

and their rationale are itemized in the decision register (Chapter A); every one of them is exposed to the F5 tuning budget. H3 is declared closed with this documented status: **these are floor numbers, not the traditional family's final word** — treating them otherwise would manufacture exactly the straw-man comparison this project exists to avoid.

## Chapter 7

# Work in progress and planning

*This chapter in brief: what is done, what is next, and the running log of every milestone with its evidence.*

### 7.1 Phase F1: closed

All four work packages of phase F1 are complete and documented in Chapter 4: calibrated design point (WP1.1), measured-data anchor calibration (WP1.2), baseline decks with fitted correction exponents and a corrected-space interpolator (WP1.3), and the ICM over a six-point operating grid with its observability analysis and the CEA cross-check (WP1.4). Milestone **H1 is declared closed** with one documented deviation from the original gate wording: the leave-one-out target of 0.1 % was set before the baseline space was chosen; the achieved corrected-space errors (medians 0.1–1 %, Table 4.4) sit at the sensor-noise floor injected in phase F2 and are common-mode to both EHM pipelines, so the gate intent —a baseline whose error does not distort the comparison— is met. Optional refinement (grid densification near block boundaries) is queued as non-blocking.

### 7.2 Phase F3: closed

Documented in Chapter 6: the traditional pipeline, its two detector-design lessons, and its v0 test-fleet scores — explicitly floor numbers pending the symmetric F5 tuning budget.

### 7.3 Phase F2: closed

Documented in Chapter 5: generator architecture, ground-truth trajectory library, snapshot and sensor models, the three gate audits (including the failed-then-fixed difficulty gate and the onset bug both audits surfaced) and the H2 declaration.

### 7.4 Remaining phases

### 7.5 Milestone log

Table 7.1: Remaining phases, key deliverables and closing criteria.

| Phase                | Key deliverable                                                                         | Closing criterion (gate)                                                                                                                                                                                                                                                                                                                                                   |
|----------------------|-----------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| F4                   | AI suite (detection, diagnosis, RUL, physics-informed hybrid, conformal intervals, PCS) | H4: beats the traditional pipeline on $\geq 1$ primary metric per task on validation                                                                                                                                                                                                                                                                                       |
| F5                   | Pre-registered evaluation + ablations + N-CMAPSS                                        | H5: hypotheses H1–H5 resolved with statistical tests; figures reproducible with one command                                                                                                                                                                                                                                                                                |
| F6                   | Case studies, dashboard, final report                                                   | H6: full reproduction from raw data; defensible document                                                                                                                                                                                                                                                                                                                   |
| <b>H2<br/>closed</b> | 2026-07-03                                                                              | SynCFM56 v1.0 frozen (Table 5.1): 100 engines, 1.58M snapshot rows, deterministic regeneration. Nonlinearity at the noise floor (Table 5.2); difficulty gate failed at 81.6 % with chronic labels, passed at 54.0 % after the acute-episode design change (Section 5.4.2); realism checks all positive; onset bug found and fixed by the audits; 25 automated tests green. |
| <b>H3<br/>closed</b> | 2026-07-03                                                                              | Traditional pipeline end-to-end on the test fleet (Table 6.1): detection recall 0.5 at 98-cycle median delay, isolation 0 % on the confusable subset, smearing index 0.85, RUL optimism funnel measured (Fig. 6.2); two detector-design lessons recorded; all defaults registered in Chapter A and exposed to the F5 budget; 31 automated tests green.                     |

Table 7.2: Milestones reached (updated at every gate).

| Milestone        | Date       | Evidence                                                                                                                                                                                                                                                                                                                                                                                                            |
|------------------|------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| H0               | 2026-07-03 | Reproducible environment (uv, Python 3.11, pyCycle 4.4 with <code>numpy&lt;2</code> ); a complete example cycle converging locally and in CI; repository skeleton and smoke test.                                                                                                                                                                                                                                   |
| H1 (partial)     | 2026-07-03 | WP1.1 and WP1.2 complete: design point inside all five acceptance windows (Table 4.1); SLS anchors calibrated against TCDS + EEDB with all three gated anchors in tolerance (Table 4.3); calibration contract with verified values.                                                                                                                                                                                 |
| H1 (WP1.3–1.4)   | 2026-07-03 | Baseline decks over the flight envelope with leave-one-out quality report (Table 4.5); health-parameter injection validated by the off-design/design self-consistency check; ICM at both snapshot conditions with SVD observability analysis — minimum cockpit signature angle $1.3^\circ$ , seven confusable pairs (Table 4.7); tabular-vs-CEA cross-check within 0.7 % (Table 4.8); twelve automated tests green. |
| <b>H1 closed</b> | 2026-07-03 | Correction exponents fitted from the model land on textbook values (Table 4.4); corrected-space baseline collapses LOO tails by an order of magnitude; ICM extended to a six-point envelope grid with stable observability (Table 4.6); computations parallelized per norm N1 (decks $2.9\times$ , ICM $6\times$ faster); sixteen automated tests green.                                                            |
| <b>H2 closed</b> | 2026-07-03 | SynCFM56 v1.0 frozen (Table 5.1): 100 engines, 1.58M snapshot rows, deterministic regeneration. Nonlinearity at the noise floor (Table 5.2); difficulty gate failed at 81.6 % with chronic labels, passed at 54.0 % after the acute-episode design change (Section 5.4.2); realism checks all positive; onset bug found and fixed by the audits; 25 automated tests green.                                          |
| <b>H3 closed</b> | 2026-07-03 | Traditional pipeline end-to-end on the test fleet (Table 6.1): detection recall 0.5 at 98-cycle median delay, isolation 0 % on the confusable subset, smearing index 0.85, RUL optimism funnel measured (Fig. 6.2); two detector-design lessons recorded; all defaults registered in Chapter A and exposed to the F5 budget; 31 automated tests green.                                                              |

# Appendix A

## Decision register

*Every material free choice made in this study, its value, and the kind of justification behind it. Justification classes: [M] measured/certified data; [L] literature range; [D] derived from our own model; [C] community convention or benchmark practice; [T] engineering default, explicitly exposed to the symmetric tuning budget of phase F5; [A] assumption with declared sensitivity. A choice justified by none of these classes would be arbitrary — the audit that produced this table found two such cases, both already resolved (noted below).*

### Engine model (F1)

| Decision                             | Value                         | Class | Basis                                                                                                            |
|--------------------------------------|-------------------------------|-------|------------------------------------------------------------------------------------------------------------------|
| Engine variant                       | CFM56-7B26                    | [C]   | most common -7B; richest public data                                                                             |
| Design point                         | M0.78 / FL350 / ISA           | [C]   | aerodynamic-design-point convention                                                                              |
| Calibration targets & tolerances     | Table 2.1;<br>$\pm 3/\pm 5\%$ | [M]   | TCDS + EEDB; tolerances set a priori in the spec                                                                 |
| Cruise thrust/TSFC targets           | 5480 lbf / 0.627              | [A]   | public type data, still flagged TO_VERIFY in the contract; H1 was gated on measured anchors only                 |
| HPC design PR                        | 9.35                          | [M]   | calibrated to the measured SLS OPR 27.61                                                                         |
| HP map speed reference               | 13 940 rpm                    | [M]   | placed so rated-thrust N2 respects the TCDS redline                                                              |
| Rating temperature $T_{4,\max}$      | 3200 °R                       | [D]   | from the calibrated takeoff anchor (Section 4.5)                                                                 |
| ICM perturbation step                | $\pm 0.5\%$                   | [C]   | central-difference standard: large enough to dominate the $10^{-8}$ solver tolerance, small enough for linearity |
| Confusable threshold                 | 15°                           | [T]   | pre-registered definition for H2; sensitivity checked implicitly by reporting all angles                         |
| Deck envelope blocks & $PC \geq 0.5$ | Section 4.5                   | [C]   | EHM trending conditions                                                                                          |
| Thermo method                        | tabular                       | [D]   | CEA cross-check within 0.7 % (Table 4.8)                                                                         |

## Synthetic fleet (F2)

| Decision                         | Value                                      | Class | Basis                                                                                                           |
|----------------------------------|--------------------------------------------|-------|-----------------------------------------------------------------------------------------------------------------|
| Degradation magnitudes/profiles  | Table 2.2                                  | [L]   | Diakunchak; Kurz & Brun                                                                                         |
| Fouling time constant            | 3000 cycles                                | [L]   | fouling saturates within months of service                                                                      |
| Wash interval / recovery         | 800–1600 cy / 30–70 %                      | [L]   | typical wash programs; recovery range from the same sources                                                     |
| New-engine EGT margin            | $85 \pm 6^\circ\text{C}$                   | [L]   | public -7B two-digit margins; per-engine scatter is a manufacturing-variability assumption [A]                  |
| Severity multiplier spread       | LogNormal (0, 0.3)                         | [A]   | produces the observed-in-service spread of lives (Table 5.1); a fleet-realism knob, not a fitted quantity       |
| Sensor noise / quantization      | catalog table                              | [L]   | typical ACARS-class instrumentation                                                                             |
| Acute-fault targets & magnitudes | 6 params, 0.4–1.5 %                        | [D]   | drawn from the ICM confusable set; magnitudes bracket the detectability edge (sub-noise to clearly visible)     |
| Acute probability / onset        | 0.5 / 30–90 % of life                      | [T]   | enough episodes per class for test statistics; onset as life fraction after the audit-found bug (Section 5.4.2) |
| Ambient scatter (takeoff dTs)    | $\mathcal{N}(10, 8)^\circ\text{C}$ clipped | [A]   | plausible mixed fleet climate; affects realism, not comparison fairness (common to both pipelines)              |
| Difficulty gate threshold        | 60 %                                       | [T]   | pre-set before the audit ran; its bite was demonstrated when the first design failed it                         |
| Splits                           | 70/10/20 by engine                         | [C]   | leakage-free standard; CI-checked                                                                               |

## Traditional pipeline (F3) and evaluation

| Decision                      | Value                                    | Class   | Basis                                                                                       |
|-------------------------------|------------------------------------------|---------|---------------------------------------------------------------------------------------------|
| Holt gains                    | $\alpha=0.15, \beta=0.05$                | [T]     | responsive-but-smooth default; swept in F5                                                  |
| CUSUM parameters              | $k=0.75\sigma, h=8$                      | [T]     | standard allowances; swept in F5                                                            |
| Gap-detector EWMA             | 0.1 / 0.005                              | [T]     | fast follows a ramp, slow spans a wash cycle; swept in F5                                   |
| Alarm persistence             | 10-of-14                                 | [T]     | multi-sample confirmation; swept in F5                                                      |
| Kalman $q$ , prior, $\lambda$ | $2 \cdot 10^{-4}$ , 2 %, 1               | [T]     | $q$ sized to chronic rates; all swept in F5                                                 |
| Wash reset fraction           | 0.5                                      | [A]     | mid-range of the catalog’s 30–70 % recovery                                                 |
| RUL window / cap              | 1500 cy / 25 000 cy                      | [T]/[C] | window spans a wash cycle; cap is NASA-benchmark practice                                   |
| NASA-score scaling            | $d/100$ cycles                           | [A]     | the PHM08 constants assume C-MAPSS-scale RUL; scaling declared, identical for both families |
| Assumed nominal margin        | $85^\circ\text{C}$                       | [A]     | fleet nominal; per-engine estimation is queued as a pipeline improvement in F5              |
| Statistical tests             | Wilcoxon, Holm, BCa                      | [C]     | pre-registered (Section 3.3)                                                                |
| $\alpha$ – $\lambda$ settings | $\alpha=20\%$ , $\lambda=\{.5, .7, .9\}$ | [C]     | common prognostics practice                                                                 |

**Audit outcome.** Sweeping the study for unjustified choices found two genuinely arbitrary decisions, both caught and resolved before this appendix was written: the *chronic-mechanism labeling* of the diagnosis task (resolved by the acute-episode redesign, Section 5.4.2) and the *acute onset drawn against the simulation horizon* rather than engine life (resolved by two-pass generation). Remaining class-[A] assumptions are declared at their point of use and shared by both EHM families, so they affect the realism of the world, not the fairness of the comparison. Class-[T] defaults are the traditional pipeline’s tuning surface — left untouched by design until F5 spends the same optimization budget on both families.



# References

- [1] Louis A. Urban. “Parameter Selection for Multiple Fault Diagnostics of Gas Turbine Engines”. In: *Journal of Engineering for Power* 97.2 (1975), pp. 225–230. DOI: 10.1115/1.3445969.
- [2] Allan J. Volponi. “Gas Turbine Engine Health Management: Past, Present, and Future Trends”. In: *Journal of Engineering for Gas Turbines and Power* 136.5 (2014), p. 051201. DOI: 10.1115/1.4026126.
- [3] Abhinav Saxena et al. “Damage Propagation Modeling for Aircraft Engine Run-to-Failure Simulation”. In: *2008 International Conference on Prognostics and Health Management*. 2008, pp. 1–9. DOI: 10.1109/PHM.2008.4711414.
- [4] Manuel Arias Chao et al. “Aircraft Engine Run-to-Failure Dataset under Real Flight Conditions for Prognostics and Diagnostics”. In: *Data* 6.1 (2021), p. 5. DOI: 10.3390/data6010005.
- [5] Eric S. Hendricks and Justin S. Gray. “pyCycle: A Tool for Efficient Optimization of Gas Turbine Engine Cycles”. In: *Aerospace* 6.8 (2019), p. 87. DOI: 10.3390/aerospace6080087.
- [6] European Union Aviation Safety Agency. *Type-Certificate Data Sheet No. E.004 for CFM56-7B Series Engines, Issue 07*. Tech. rep. <https://www.easa.europa.eu/en/document-library/type-certificates/engine-cs-e/easae004-cfm-international-sa-cfm56-7b-series>. EASA, Jan. 2023.
- [7] International Civil Aviation Organization. *ICAO Aircraft Engine Emissions Databank, edition 03/2026*. Hosted by EASA. <https://www.easa.europa.eu/en/domains/environment/icao-aircraft-engine-emissions-databank>. 2026.
- [8] SAE International. *ARP755A: Gas Turbine Engine Performance Station Identification and Nomenclature*. Tech. rep. SAE, 1974.
- [9] Y. G. Li. “Performance-analysis-based gas turbine diagnostics: A review”. In: *Proceedings of the Institution of Mechanical Engineers, Part A: Journal of Power and Energy* 216.5 (2002), pp. 363–377. DOI: 10.1243/095765002320877856.
- [10] Ihor S. Diakunchak. “Performance Deterioration in Industrial Gas Turbines”. In: *ASME 1991 International Gas Turbine and Aeroengine Congress and Exposition*. Journal of Engineering for Gas Turbines and Power, 114(2):161–168. 1992. DOI: 10.1115/1.2906565.
- [11] Rainer Kurz and Klaus Brun. “Fouling Mechanisms in Axial Compressors”. In: *Journal of Engineering for Gas Turbines and Power* 134.3 (2012), p. 032401. DOI: 10.1115/1.4004403.
- [12] Justin S. Gray et al. “OpenMDAO: An open-source framework for multidisciplinary design, analysis, and optimization”. In: *Structural and Multidisciplinary Optimization* 59 (2019), pp. 1075–1104. DOI: 10.1007/s00158-019-02211-z.